


City of Gonzales


Building Services Department

147 Fourth Street Gonzales, CA 93926 P.O. Box 647 Phone: (831) 675-5000 FAX: (831) 675-2644 https://gonzalesca.gov/

AGING-IN-PLACE DESIGN AND FALL PREVENTION REQUIREMENTS

These illustrations are intended for new residential projects, including ADUs; and the requirements are based on the 2022 California Residential Code Section R327.





EFFECTIVE JULY 2024

AT LEAST ONE BATHROOM AND ONE BEDROOM ON THE ENTRY LEVEL MUST PROVIDE A DOORWAY WITH A NET CLEAR OPENING OF NOT LESS THAN 32-INCHES MEASURED WITH THE DOOR POSITIONED AT AN 90 DEGREE ANGLE.

IN A 2- OR 3- STORY SFD, THIS REQUIREMENT APPLIES TO THE E SECOND OR THIRD FLOOR IF A BATHROOM OR BEDROOM IS NOT LOCATED ON THE ENTRY LEVEL.

NOTES:

- Reinforcement must be located between the dimensions specified.
- Reinforcement must be continuous in bathtub, bathtub combo and shower wall enclosures, where wall framing is provided.
- Reinforcement may be solid lumber or other construction materials that provide equal height and load capacity.
- The location of the reinforcement must be incorporated in the Operation and Maintenance Manual (e.g., floor plan and elevation details) required by CAL Green Section 4.410.1.
- Additional back wall reinforcement must be installed with the bottom edge no more than 6-inches above the bathtub rim.
- 6. The suggested dimensions are to accommodate the minimum required 36-inches clearance, center to center, at a water closet; and minimum 24-inches clear space in front of water closet (<u>CPC 402.5</u>). At this time <u>CRC R327</u> does not specify the minimum lengths at these locations.

EXCEPTIONS:

- Reinforcement for future floor-mounted, foldaway, or similar alternate grab bar may be installed with prior approvals from the enforcing agency.
- Wall reinforcement is not required where prefabricated shower & bathtub panels that have integral factory-installed grab bars, or when factory-installed reinforcement for grab bars is provided.
- 3. Reinforcement of floor is not required for bathtubs and water closets installed on concrete floors.
- Dedicated receptacle outlets; floor receptacle outlets; controls mounted on ceiling fans and ceiling lights and controls located on appliances; and required receptacles on a wall space that has a built-in feature above finish floor less than 15-inches.